KOLAR DIVISION.

The 15th February 1897.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Kolar division, up to 8th March 1897, for opening out right bank channel of Ramasamudra Tank, Sidlaghatta taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1898.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Kolar between the hours of 11 A. M. and 5 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer and accompanied by a statement, in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 200 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for opening out right bank channel of Ramasamudra Tank," in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

ABSTRACT.

Description of work.	*Per.*	*Quantity.*
Preliminary charges—		
Levelling lock spitting trial pits, &c.	L. S.	350
Removing loose stones and boulders both embedded and loose. Removing embedded boulders and stones.	C. yds.	1,120
Removing surface boulders and big stones	do	400
Blasting—		
Surface blasting	do	46
In the excavation	do	324
Excavation in rocky or bouldry soil	do	979
Do in soft rock	do	396
Cutting hard rock disintegrated rock	do	295
Embankment requiring consolidation for channel. Ordinary embankment.	do	5,099
Puddle work	do	6,624
Excavation in hard gravelly soil	do	1,303
Do in ordinary soil including white soft stuff below and carrying and forming, &c.	do	25,794
Revetment	do	1,200
Masonry wall on rock—		
Preparing the foundation	L. S.	10
Burnt brick in surki mortar	C. ft.	447
Burnt stone slabs 3" thick including dressing, fixing, &c.	S. ft.	108
Fine plastering with surki mortar	Sq.	4·50
Aqueduct No. II—		
Clearing the site, excavating foundation and re-filling sides	L. S.	40
Burnt stone in chunam plain work	C. ft.	4,901
Do arch work including scaffolding and centering	do	244
Burnt brick in surki mortar	do	581
Concrete	do	30
Burnt stone slabs 4½"	S. ft.	155
Do 4"	do	149
Do 3"	do	100
Rough stone work	C. yds.	76
Pointing	Sqr.	17·40
Fine plastering	do	5·50

Description of work.		Per.	Quantity.
Relieving weir No. 1—			
Clearing site, excavating foundation, refilling, &c.		L. S.	25
Burnt stone in chunam		C. ft.	316
Burnt brick in surki mortar		do	358
Burnt stone slabs	7″	S. ft.	18
Do	6″	do	135
Do	3″	do	53
Rough stone work		C. yds.	12
Cutting joint		Each	2
Cutting groves for the shutters		L. S.	8
Teak wood shutters		Each	1
Fine plastering		Sqr.	1·29
Concrete below slabbed apron		C. ft.	37
Relieving weir No. 2—			
Clearing the site, excavating foundation, &c.		L. S.	30
Burnt stone in chunam		C. ft.	445
Burnt brick in surki mortar		do	445
Burnt stone slabs	7″	S. ft.	19
Do	6″	do	202
Do	3″	do	53
Rough stone work		C. yds.	12
Cutting joints		Each	2
Cutting groves for shutters		L. S.	8
Teak wood shutters, each		...	1
Fine plastering		Sqr.	1·72
Concrete below slabbed apron		C. ft.	54
Relieving weir No. 3—			
Clearing site, excavating foundation, &c.		L. S.	25
Burnt stone in chunam		C. ft.	476
Burnt brick in surki mortar		do	428
Burnt stone slabs	7″	S. ft.	18
Do	6″	do	202
Do	3″	do	53
Rough stone work		C. yds.	12
Cutting joints		Each	2
Cutting groves for shutters		L. S.	8
Teak wood shutters, each		...	1
Fine plastering		Sqr.	1·50
Concrete below slabbed apron		C. ft.	54
Relieving weir No. 4—			
Clearing site, excavating foundation, re-filling, &c.		L. S.	20
Burnt stone in chunam		C. ft.	306
Burnt brick in surki mortar		do	320
Burnt stone slabs	7″	S. ft.	26
Do	6″	do	121
Do	3″	do	53
Rough stone work		C. yds.	12
Cutting joints		Each	2
Cutting groves for shutters		L. S.	8
Teak wood shutters		Each	1
Fine plastering		Sqr.	1·10
Concrete below slabbed apron		C. ft.	33
Relieving weir No. 5—			
Clearing site, &c.		L. S.	15
Burnt stone in chunam		C. ft.	278
Burnt brick in surki mortar		do	308
Burnt stone slabs	6″	S. ft.	100
Do	3″	do	53
Rough stone work		C. yds.	7
Cutting joints		Each	1
Fine plastering		Sqr.	1·04
Concrete below slabbed apron		C. ft.	25
Relieving weir No. 6—			
Clearing site, &c.		L. S.	35
Burnt stone in chunam		C. ft.	445
Burnt brick in surki mortar		do	374
Burnt stone slabs	7″	S. ft.	15
Do	6″	do	203
Do	3″	do	53
Rough stone work		C. yds.	12
Cutting joints		Each	2
Cutting groves for shutters		L. S.	8

Description of work.		*Per.*	*Quantity.*
Relieving weir No. 7—			
Clearing site, &c.		L. S.	30
Burnt stone in chunam		C. ft.	420
Burnt brick in surki mortar		do	389
Burnt stone slabs	7″	S. ft.	15
Do	6″	do	135
Do	3″	do	53
Rough stone work		C. yds.	12
Cutting joints		Each	2
Cutting groves for shutters		L. S.	8
Teak wood shutters		Each	1
Fine plastering		Sqr.	1·03
Concrete below slabbed apron		C. ft.	37
Cattle bridge No. 1—			
Excavating foundation filling,		L. S.	3
Burnt stone in chunam		C. ft.	292
Burnt brick in surki mortar		do	41
Burnt stone slabs	6″	S. ft.	129
Do	3″	do	24
Guard stones		Each	4
Rough stone wings		C. yds.	14
Fine plastering		Sqr.	0·75
Pointing		do	2·50
Romps		L. S.	5
Cattle bridge No. 2—			
Excavating foundation, re-filling, &c.		do	2
Burnt stone in chunam		C. ft.	292
Burnt brick in surki mortar		do	35
Burnt stone slabs	6″	S. ft.	113
Do	3″	do	20
Guard stones		Each	4
Rough stone wings		C. yds.	14
Fine plastering		Sqr.	0·75
Pointing		do	2·50
Romps		L. S.	5
Cattle bridge No. 3—			
Excavating foundation, re-filling, &c.		do	2
Burnt stone in chunam		C. ft.	211
Burnt brick in surki mortar		do	28
Burnt stone slabs	6″	S. ft.	90
Do	3″	do	16
Guard stones		Each	4
Rough stone wings		C. yds.	14
Fine plastering		Sqr	0·50
Pointing		do	1·50
Romps		L. S.	5
Cattle bridge No. 4—			
Excavating foundation and re-filling, &c.		do	2
Burnt stone in chunam		C. ft.	211
Burnt brick in surki mortar		do	18
Burnt stone slabs	6″	S. ft.	62
Do	3″	do	10
Guard stones		Each	4
Rough stone wings		C. yds.	14
Fine plastering		Sqr.	0·50
Pointing		do	1·50
Romps		L. S.	5
Madabays—			
Excavating foundation, &c.		do	5
Burnt brick in surki mortar		C. ft.	131
Concrete		do	6
Burnt stone slabs	3″	S. ft.	91
Cutting groves for shutters		L. S.	2
Fine plastering		Sqr.	2·00
One shutter with rods, iron nails, &c., complete		L. S.	10
Total eleven Madabays of above details			
Miscellaneous—			
Mile stones		Each	5
Index stones		do	64
Bed grade stones		do	72
Compensation for land required for earthwork, &c.		L. S.	600

V. ARUNACHELLA MUDALIAR, *Offg. Executive Engineer.*